

- A. Traffic Requirements - The following is a general overview of the traffic control and staging required throughout all stages of the project. The staging requirements are described further in the "Prosecution and Progress" article in the special provisions.

Accomplish the construction sequence, including the associated traffic control as detailed in the Construction Staging section of the plans, and as described in this Traffic article.

Do not begin or continue any work that closes traffic lanes outside the allowed time periods specified in this article.

STH 21, STH 80, CTH G and local roads will remain open to through traffic at all times for the duration of this project except where noted below and in the Prosecution and Progress article of these special provisions.

Do not deliver or store materials and equipment within open travel lanes or open side roads during any stage of construction.

Conduct operations in a manner that will cause the least interference to traffic and pedestrian movements. Maintain vehicle and pedestrian access at all times to properties within the limits of construction. Access to parcels may be restricted for up to one calendar day in order to construct driveways. Notify property owners at least **five calendar days** prior to closing their access point. Maintaining property access is incidental to the Traffic Control bid item.

Flagging operations will be allowed along all roadways to accommodate the roadway work between 1 hour after sunrise and 1 hour before sunset. Use sunset and sunrise information from the nearest National Weather Service office. Delays due to flagging may not exceed 15 minutes in any direction. The engineer will have the ability to suspend work activities in the event any undesirable traffic congestion develops that has the potential to cause lengthy motorist delay or unsafe workings conditions.

Coordinate and stage all construction activities within the areas of local traffic routes, as required to maintain a traveled way conforming to all above requirements.

Do not switch traffic over to the next construction stage until all signing, pavement marking, reflectors, lighting, tubular marker posts, barricades, and traffic control drums for the stage are in place, temporary signals for the stage are in place and operational, and conflicting pavement markings and signs are removed as shown in the traffic control and temporary signal plans and as directed by the engineer. Traffic control shall be completely in place by the end of the working day of a traffic switch.

1. Access Requirements

- a. Pedestrian accommodations (See Specials Pg. 8 of 34)
- b. Resident accommodations (See Specials Pg. 8 of 34)
- c. Business accommodations (See Specials Pg. 8 of 34)
- d. Emergency service accommodations
 - Notify the following emergency and local officials 48 hours in advance of the start of work, closures of existing streets, and prior to traffic control changes. Notifications must be given by 4:00 PM on Thursday for any such work to be done on the following Monday.
 - Wisconsin State Patrol
 - Juneau County Sheriff's Department
 - Juneau County Highway Department
 - Town of Necedah
 - Village of Necedah